

T. 4 N., R. 28 E., W.M.

Chains	Feet
	<u>Section 15</u>
	I set 2 x 4 ins. stake mkd. 1/16 on line in its correct position, that is, 20.05 chs. from SW cor. of sec.
	<hr/>
	The $\frac{1}{4}$ cor. bet. secs. 15 & 16 being visible from SW cor. sec., I ran
	N. 0° 13' W. along W. Bdy. of sec. 15 and the SW cor.
20.00	Set trial 1/16 cor. on line.
40.00	$\frac{1}{4}$ cor. bet. Secs. 15 & 16.
	Trail cor. being in its right position I set 2 x 4 ins. stake mkd. 1/16 in this position.
	<hr/>
	The NW cor. of sec. 15 being visible from the above $\frac{1}{4}$ cor. I ran
	N. 0° 8' E. along W. Bdy. of sec. 15 from the above $\frac{1}{4}$ cor.
40.00	NW cor. sec. 15.
	<hr/>
	By intersection of $\frac{1}{4}$ lines I placed 2 x 4 ins. stake mkd. 1/16 at center of the sec.
	<hr/>
	Center of sec. being visible from the $\frac{1}{4}$ cor. bet. secs. 15 and 22
	I ran
	N. 0° 07' W. along $\frac{1}{4}$ line from above $\frac{1}{4}$ cor.
20.00	Set trial 1/16 cor. on line.
40.08	1/16 cor. center of sec.
50.08	Set trial NW cor. of Farm Unit M.
60.08	" " 1/16 cor. for NW cor. Farm Unit L
80.08	$\frac{1}{4}$ cor. bet. secs. 10 and 15.
	Set 2 x 4 stake mkd. 1/16 in its correct position, that is, 20.04 chs. on line from $\frac{1}{4}$ cor. bet. secs. 15 & 22.
	Trial NW cor. Farm Unit M and 1/16 cor. at NW cor. Farm Unit L being in correct positions, I replaced them by a 2 x 2 ins. stake and 2 x 4 ins. stake mkd. 1/16.
	<hr/>