

1st Standard Parallel N., R. 30 E., W.M.
 Surveyed by H. J. G. Maxon & Jared S. Hurd, U.S. Deputy Surveyors
 Under Contract No. 50
 Dated Feb. 2, 1860

Chains		Feet
	From cor. to Tp. 5 N., of Rgs. 29 & 30 E., I run W. on th S. Bdy. of Sec. 36	
	Var. 18° E.	
40.00	Set post for $\frac{1}{4}$ Sec. Cor. in mound of earth, trench & pits as per instructions.	
80.00	Set post for cor. to Secs. 35 & 36 in mound of earth & trench and pits as per instructions. Soil; poor & sandy, grass good, scattering patches of sage & grease wood. Gently rolling.	
	W. on S. Bdy. of Sec. 35	
	Var. 18° E.	
40.00	Set post for $\frac{1}{4}$ Sec. cor. in mound of earth, trench & pits as per instructions.	
68.00	Dry ravine br. S.W. and N.E.	
80.00	Set post for Cor. Secs. 34 & 35 in mound of earth, trench and pits as per instructions. Soil; clay and sand, good grass, gently rolling.	
	W. on S. Bdy. of Sec. 34	
	Var. 18° E.	
40.00	Set post for $\frac{1}{4}$ Sec. Cor. in mound of earth, trench and pits as per instructions.	
80.00	Set post for Cor. to Secs. 33 & 34 in mound of earth, trench and pits as per instructions. Soil; clay and sand, grass good. Scattering sage & grease wood. Land; gently rolling	
	May 5th 1860	
	W. on S. Bdy. of Sec. 33	
	Var. 18° E.	
11.50	Trail brs. S. 22° W. & N. 22° E.	
18.75	Trail brs. N. and S.	
38.56	Dry ravine brs. N. and S.	