

## Subdivisional Lines of T. 4 N., R. 29 E., W.M.

Chains		Feet
	N. bet. Secs. 1 & 2	
		Var. 21° E.
16.00	Foot of rise or table	
23.00	A dry run, 20 lks. wide, runs, N.W.	
40.00	Set $\frac{1}{4}$ Sec. Cor. post in mound with charred stake as per instructions.	
79.50	Intersect the first Standard Parallel, N. 8.22 Chs. W. of Cor. to Secs. 35 & 36	
	T. 5 N., R. 29 E.	
<hr/>		
	Tuesday Sept. 3rd, 1861.	
	Resurveyed the S. Bdy. of Sec. 35 & found it bearing, S. 89° 45' W.	
<hr/>		
	N. bet. Secs. 34 & 35	
		Var. 21° E.
40.00	Set $\frac{1}{4}$ Sec. Cor. post in mound with charred stake as per instructions.	
80.00	Set post in mound with charred stake as per instructions. Cor. to Secs. 26, 27, 34 & 35	
	Land; undulating, some sandy with bunch grass only.	
<hr/>		
	E. on random bet. Secs. 26 & 35	
		Var. 21° E.
40.00	Set temp. $\frac{1}{4}$ Sec. post	
79.90	Intersect N. & S. line, 40 lks. S. of Sec. Cor. S. 89° 43' W. on true line bet. Secs. 26 & 35	
39.95	Set $\frac{1}{4}$ Sec. Cor. post in mound with charred stake as per instructions.	
79.90	To Cor. of Secs. 26, 27, 34 & 35	
	Soil, surface etc., as in the preceeding mile.	
<hr/>		
	N. bet. Secs. 26 & 27	
		Var. 21° E.
40.00	Set $\frac{1}{4}$ Sec. Cor. post in mound with charred stake as per instructions.	