

Subdivisional Lines of T. 4 N., R. 29 E., W.M.

Chains		Feet
	N. bet. Secs. 28 & 29	
		Var. 20° 20' E.
25.00	Branch of Walla Walla trail, course N.E.	
40.00	Set $\frac{1}{4}$ Sec. post in mound with charred stake as per instructions.	
80.00	Set post cor. to Secs. 20, 21, 28 & 29, with charred stake in mound as per instructions.	
<hr/>		
	E. on random bet. Secs. 21 & 28	
		Var. 20° 30' E.
40.00	Set temp. $\frac{1}{4}$ Sec. post	
73.93	Intersect N. & S. line, 1.00 S. of the Secs Cor. S. 89° 17' W. on true line	
39.46 $\frac{1}{2}$	Set $\frac{1}{4}$ Sec. post in mound with charred stake as per instructions.	
54.43	Walla Walla trail, N.E. course	
78.93	To Cor. of Secs. 20, 21, 28 & 29 Soil; sandy, Surface; undulating, but not at all broken, with sage, greasewood, cactus, yarrow, flax and bunch grass, as usually.	
<hr/>		
	N. bet. Secs. 20 & 21	
		Var. 20° 30' E.
40.00	Set $\frac{1}{4}$ Sec. post in mound with charred stake as per instructions.	
80.00	Set post Cor. to Secs. 16, 17, 20 & 21, with charred stake in mound as per instructions. Soil; surface etc. as in the preceding mile.	
<hr/>		
	E. on random bet. Secs. 16 & 21	
		Var. 21° E.
40.00	Set temp. $\frac{1}{4}$ Sec. post.	
79.33	Intersect N. & S. line, 90 lks S. of Sec. Cor. S. 89° 21' W. on true line	