

Subdivisional Lines of T. 4 N., R. 29 E., W.M.

Chains		Feet
80.05	To Cor. of Secs. 29, 30, 31 & 32 Soil; surface and productions as in the land off the stream, vig. sandy soil; undulating surface with sage, grease- wood, cactus, yarrow, dwarf sun flower, bunch grass & in some places, flax.	
	W. on random bet. Secs. 30 & 31. Var. 20° 30' E.	
40.00	Set temp. $\frac{1}{4}$ Sec. post	
88.50	Intersect W. Bdy. of the T. 25 lks N. of Sec. Cor. N. 89° 49' E. on true line bet. Secs. 30 & 31	
11.50	Road to Umatilla landing, course N.W.	
48.50	Set $\frac{1}{4}$ Sec. Cor. in mound with charred stake as per instruc- tions.	
88.50	To Cor. of Secs. 29, 30, 31 & 32 N. bet. Secs. 29 & 30 Var. 20° 30' E.	
40.00	Set $\frac{1}{4}$ Sec. post in mound with charred stake as per in- structions.	
80.00	Set post Cor. to Secs. 19, 20, 29 & 30, in mound with charred stake as per instructions.	
40.00	E. on random bet. Secs. 20 & 29 Var. 20° 36' E.	
80.08	Intersect N. & S. line, 53 lks. S. of Sec. Cor. S. 89° 37' W. on true line bet. Secs. 20 & 29	
40.04	Set $\frac{1}{4}$ Sec. post in mound with charred stake as per instruc- tions.	
80.08	To Cor. of Secs. 19, 20, 29 & 30. W. on random bet. Secs. 19 & 30 Var. 20° 36' E.	
40.00	Set temp. $\frac{1}{4}$ Sec. post	
88.30	Intersect W. Bdy. of T., 15 lks. N. of Sec. Cor.	