

Subdivisional Lines of T. 4 N., R. 29 E., W.M.

Chains		Feet
	N. 89° 54' E. on true line bet. Secs. 19 & 30	
48.30	Set $\frac{1}{4}$ Sec. Cor. post in mound with charred stake as per instructions.	
88.30	To Cor. of Secs. 19, 20, 29 & 30 Soil; sandy Surface; slightly undulating with sage, bunch grass etc.	
<hr/>		
	N. bet. Secs. 19 & 20	
		Var. 20° 36' E.
40.00	Set $\frac{1}{4}$ Sec. post in mound with charred stake as per instructions.	
80.00	Set post Cor. to Secs. 17, 18, 19 & 20, in mound with charred stake, as per instructions. Soil: & surface etc. as before. Mt. Hood, brs. S. 76 $\frac{1}{2}$ ° W.	
<hr/>		
	E. on random bet. Secs. 20 & 17	
		Var. 20° 30' E.
40.00	Set temp. $\frac{1}{4}$ Sec. post	
79.75	Intersect N. & S. line, 46 lks. S. of Sec. Cor. S. 89° 40' W. on true line bet. Secs. 18 & 19	
39.87 $\frac{1}{2}$	Set $\frac{1}{4}$ Sec. post in mound with charred stake as per instructions.	
79.75	To Cor. of Secs. 17, 18, 19 & 20.	
<hr/>		
	W. on random bet. Secs. 18 & 19	
		Var. 20° 30' E.
40.00	Set temp. $\frac{1}{4}$ Sec. post	
88.10	Intersect W. Bdy. of the T., 44 lks. N. of the Cor. to Secs. 18, & 19. N. 89° 42' E. on true line bet. Secs. 18 & 19	
48.10	Set $\frac{1}{4}$ Sec. Cor. in mound with charred stake, as per instructions.	
88.10	To Cor. of Secs. 17, 18, 19 & 20.	