

## Subdivisional Lines of T. 4 N., R. 29 E., W.M.

Chains		Feet
	Sunday, Sept. 8th, 1861.	
	N. bet. Secs. 17 & 18	
	Var. 20° 30' E.	
40.00	Set $\frac{1}{4}$ Sec. post in mound with charred stake as per instructions.	
80.00	Set post Cor. to Secs. 7, 8, 17 & 18, in mound with charred stake as per instructions.	
	Soil; sandy	
	Surface; undulating, productions as before, Sage, Greasewood & Bunch grass.	
<hr/>		
	E. on random bet. Secs. 8 & 17	
	Var. 20° 45' E.	
40.00	Set temp. $\frac{1}{4}$ Sec. post	
80.16	Intersect N. and S. line, 25 lks. S. of Sec. Cor.	
	S. 89° 49' W. on true line bet. Secs. 8 & 17	
80.08	Set $\frac{1}{4}$ Sec. Cor. in mound with charred stake as per instructions.	
80.16	To Cor. of Secs. 7, 8, 17 & 18	
<hr/>		
	W. on random bet. Secs. 7 & 18	
	Var. 20° 45' E.	
40.00	Set temp. $\frac{1}{4}$ Sec. post	
87.76	Intersect W. Bdy. of the Tp., 52 lks. N. of Sec. Cor.	
	N. 89° 37' E. on true line bet. Secs. 7 & 18	
47.76	Set $\frac{1}{4}$ Sec. post in mound with charred stake as per instructions.	
87.76	To Cor. of Secs. 7, 8, 17 & 18.	
<hr/>		
	N. bet. Secs. 7 & 8	
	Var. 20° 45' E.	
40.00	Set $\frac{1}{4}$ Sec. post in mound with charred stake as per instructions.	
80.00	Set Cor. to Secs. 5, 6, 7 & 8, in mound with charred stake as per instructions.	