

E. Bdy. of T. 4 N., R. 30 E., W.M.

Chains		Feet
	N. bet. Secs. 1 & 6	
		Var. 20° 10' E.
40.00	Set post for $\frac{1}{4}$ Sec. Cor., and built mound of earth with pits, trench, etc., as per instructions.	
79.25	Indian Trail, from Umatilla to Walla Walla, brs. N.W.&S.E	
80.00	Set post for cor. to Tp. No. 4 & 5 N. of Rgs. 30 & 31 E. and built mound of earth with pits, trench, etc. as per instructions.	
	Land; gently rolling	
	Soil; 2nd rate.	
	Note:- The quality of land in Tp. 4 N. of Rgs. 30 & 31 E. Generally a level grass plain. No water or timber.	
		Aug. 8th 1880.
Subdivisional Lines of T. 4 N., R. 30 E., W.M. As surveyed by Dolphus S. Payne, U.S. Deputy Surveyor Under Contract No. 100, Dated August 1st, 1861.		
		Sept. 7, 1861.
	Having adjusted my compass to correspond with the Guide Meridian (E. Bdy., R. 30.)	
	Began at the S.W. Cor. of Sec. 36	
		Var. 20° 13' E.
	N. on line bet. Secs. 35 & 36	
29.00	Middle of Ravine, about 3.00 Chs. wide, course W.	
40.00	Set charred stake, with mound, trench and pits as per instructions, for $\frac{1}{4}$ Sec. Cor.	
80.00	Set charred stake, with mound, trench and pits as per instructions, for Cor. to Secs. 25, 26, 35 & 36.	
		Var. 19° 45' E.
	Soil; good	
	Land; level	
	E. on random bet. Secs. 25 & 36.	
40.00	Set temp. $\frac{1}{4}$ Sec. post	
79.93	Intersect T. line, 65 lks. S. of Cor. to Secs. 25 & 36 S. 89° 33' W. on true line bet. Secs. 25 & 36	