

## Subdivisional Lines of T. 4 N., R. 30 E., W.M.

Chains		Feet
16.00	Indian trail, N. 45° W.	
39.96	Set charred stake with mound, trench and pits, as per instructions, for $\frac{1}{4}$ Sec. Cor.	
79.93	Cor. to Secs. 25, 26, 35 & 36 Land; rolling Soil; 2nd rate.	
<hr/>		
	N. on line bet. Secs. 25 & 26	
40.00	Set charred stake, with mound, trench and pits, as per instructions., for $\frac{1}{4}$ Sec. Cor.	
58.00	Indian Trail, N. 45° W.	
80.00	Set charred stake, with mound, trench and pits as per instructions, for Cor. to Secs. 23, 24, 25 & 26. Var. 19° 45' E. Soil; 2nd rate.	
<hr/>		
	E. on random bet. Secs. 24 & 25	
40.00	Set temp. $\frac{1}{4}$ Sec. post	
80.50	Intersect T. line, 40 lks. S. of Cor. to Secs. 24 & 25 S. 89° 42' W. on true line bet. Secs. 24 & 25	
8.00	Ravine, N. 80° W., 2.00 Chs. wide	
25.00	Ravine, N. 80° W., about 2.00 Chs. wide.	
40.25	Set charred stake, with mound, pits & trench, as per instructions, for $\frac{1}{4}$ Sec. Cor.	
71.00	Middle of Ravine, N. 80° W.	
72.80	Indian Trail, N. 80° W.	
80.50	Cor. to Secs. 23, 24, 25 & 26 Bottom of ravines, sandy Soil; 2nd rate.	
<hr/>		
	N. on line bet. Secs. 23 & 24	
4.50	Ravine, course W.	
10.00	Indian trail, N. 30° W.	
40.00	Set charred stake, with mound, trench and pits as per instructions, for $\frac{1}{4}$ Sec. Cor.	