

Subdivisional Lines of T. 4 N., R. 30 E., W.M.

Chains		Feet
	N. in line bet. Secs. 26 & 27	
40.00	Set charred stake, with mound, trench and pits as per instructions, for $\frac{1}{4}$ Sec. Cor.	
80.00	Set charred stake, with mound, trench and pits as per instructions, for Cor. to Secs. 22, 23, 26 & 27 Var. 19° 45' E.	
	Soil; 2nd rate.	
<hr/>		
	E. on random bet. Secs. 23 & 26	
40.00	Set temp. $\frac{1}{4}$ Sec. post	
79.78	Intersect Sec. line, 23 lks. S. of Cor. to Secs. 23, 24, 25 & 26	
39.89	S. 89° 15' W. on true line bet. Secs. 23 & 26. Set charred stake, with mound, trench and pits as per instructions, for $\frac{1}{4}$ Sec. Cor.	
63.00	Indian Trail, N. 45° W.	
79.78	Cor. to Secs. 22, 23, 26 & 27 Land; rolling Soil; 2nd rate.	
<hr/>		
	N. on line bet. Secs. 22 & 23	
40.00	Set charred stake, with mound, trench & pits as per instruction, for $\frac{1}{4}$ Sec. Cor.	
51.50	Indian Trail, N. 45° W.	
55.00	Middle of Ravine, 3.00 Chs. wide, (N. 45° W.)	
80.00	Set charred stake, with mound, trench and pits as per instructions, for Cor. to Secs. 14, 15, 22 & 23 Var. 20° 06' E.	
	Soil; 2nd rate Bottom of ravine, sandy.	
<hr/>		
	E. on random bet. Secs. 14 & 23	
40.00	Set temp. $\frac{1}{4}$ Sec. post	
80.00	Intersect Sec. line, 34 lks. S. of Cor. to Secs. 13, 14, 23 & 24 S. 89° 45' W. on true line, bet. Secs. 14 & 23.	
40.00	Soil; 2nd rate. Set charred stake with mound, trench and pits as per instructions	