

Subdivisional Lines of T. 4 N., R. 30 E., W.M.

Chains		Feet
80.50	Intersect Sec. line at post Cor. to Secs. 1, 2, 11 & 12 Soil; 2nd rate.	
<hr/>		
N. on line bet. Secs. 2 & 3		
40.00	Set temp. $\frac{1}{4}$ Sec. post	
73.97	Intersect Standard Parallel at 46 lks. W. of post Cor. to Secs. 2 & 3, T 4 N and 34 & 35 T 5 N. R 30 E.	
S. 20' W. on true line bet. Secs. 2 & 3		
33.97	Set charred stake, with mound, trench and pits as per instructions, for $\frac{1}{4}$ Sec. Cor.	
73.97	Cor. to Secs. 2, 3, 10 & 11 Soil; 2nd rate.	
<hr/>		
N. on line bet Secs. 33 & 34		
Var. 20° 30' E.		
9.50	Ravine (W.), 4.00 Chs. wide	
40.00	Set charred stake, with mound, trench and pits as per instructions, for $\frac{1}{4}$ Sec. Cor.	
80.00	Set charred stake, with mound, trench & pits as per in- structions, for Cor. to Secs. 27, 28, 33 & 34	
Var. 20° 18' E.		
Soil; 2nd rate.		
<hr/>		
E. on random bet. Secs. 27 & 34		
40.00	Set Temp $\frac{1}{4}$ Sec. post	
79.90	Intersect Sec. line, 10 lks. S. of Cor. to Secs. 26, 27, 34 & 35	
S. 89° 56' W. on true line bet. Secs. 27, & 34.		
39.95	Set charred stake, with mound, trench & pits as per in- structions, for $\frac{1}{4}$ Sec. Cor.	
79.90	Cor. to Secs. 27, 28, 33 & 34	
<hr/>		
N. on line bet. Secs. 27 & 28		
40.00	Set charred stake, with mound, trench & pits as per instructions, for $\frac{1}{4}$ Sec. Cor.	