

Subdivisional Lines of T. 4 N., R. 30 E., W.M.

Chains		Feet
40.00	Set charred stake, with mound, trench and pits as per instructions, for $\frac{1}{4}$ Sec. Cor.	
80.00	Set charred stake, with mound, trench and pits as per instructions, for Cor. to Secs. 8, 9, 16 & 17 Var. 20° 24' E. Land; on this mile light, loose & sandy, very poor.	
E. on random bet. Secs. 9 & 16		
40.00	Set temp. $\frac{1}{4}$ Sec. post	
80.20	Intersect Sec. line, 24 lks. N. of Cor. to Secs. 9, 10, 15 & 16 N. 89° 50' W. on true line bet. Secs. 9, & 16	
40.10	Set charred stake, with mound, trench and pits as per instructions, for $\frac{1}{4}$ Sec. Cor.	
80.20	Cor. to Secs. 8, 9, 16 & 17	
September 11th		
N. on line bet. Secs. 8 & 9		
40.00	Set charred stake, with mound, trench and pits as per instructions, for $\frac{1}{4}$ Sec. Cor.	
80.00	Set charred stake, with mound, trench and pits as per instructions, for Cor. to Secs. 4, 5, 8 & 9 Var. 20° 45' E. Land; sandy, Soil; poor.	
E. on random bet. Secs. 4 & 9		
40.00	Set temp. $\frac{1}{4}$ Sec. post	
80.00	Intersect Sec. line, 35 lks. S. of Cor. to Secs. 3, 4, 9 & 10. S. 89° 45' W. on true line, bet. Secs. 4 & 9	
40.00	Set charred stake, with mound, trench and pits as per instructions, for $\frac{1}{4}$ Sec. Cor.	
80.00	Cor. to Secs. 4, 5, 8 & 9 Soil; 2nd rate.	