

Subdivisional Lines of T. 4 N., R. 30 E., W.M.

Chains		Feet
46.70	Set charred stake, with mound, trench and pits as per instructions, for $\frac{1}{4}$ Sec. Cor.	
86.70	Cor. to Secs. 29, 30, 31 & 32.	
September 12th		
N. on line bet. Secs. 29 & 30		
40.00	Set charred stake, with mound, trench, pits, as per instructions, for $\frac{1}{4}$ Sec. Cor.	
80.00	Set charred stake, with mound, trench and pits as per instructions, for Cor. to Secs. 19, 20, 29 & 30. Var. 20° E.	
Soil; 2nd rate.		
E. on random bet. Secs. 20 & 29		
40.00	Set temp. $\frac{1}{4}$ Sec. post	
79.70	Intersect Sec. line, 13 lks. S. of Cor. to Secs. 20, 21, 28 & 29.	
S. 89° 55' W. on true line bet. Secs. 20 & 29.		
39.85	Set charred stake, with mound, trench and pits as per instructions, for $\frac{1}{4}$ Sec. Cor.	
79.70	Cor. to Secs. 19, 20, 29 & 30 Soil; 2nd rate.	
Closing Cor. being in sight, run		
S. 89° 10' W. on true line bet. Secs. 19 & 30		
40.00	Set charred stake, with mound, trench and pits as per instructions, for $\frac{1}{4}$ Sec. Cor.	
86.25	Intersect Tp. line at post Cor. to Secs. 19, 30, R 30 E., & 24, 25, R. 29 E. Soil; 2nd rate.	
N. on line bet. Secs. 19 & 20		
40.00	Set charred stake, with mound, trench & pits as per instructions, for $\frac{1}{4}$ Sec. Cor.	
80.00	Set charred stake, with mound, trench and pits as per instructions, for Cor. to Secs. 17, 18, 19 & 20.	