

Subdivisional Lines of T. 4 N., R. 30 E., W.M.

Chains		Feet
39.80	Set charred stake, with mound, trench and pits as per instructions, for $\frac{1}{4}$ Sec. Cor.	
79.60	Cor. to Secs. 7, 8, 17 & 18 Soil; sandy, 3rd rate.	
40.00	Closing Cor. being in sight, run S. 89° 30' W. on true line bet. Secs. 7 & 18 Set charred stake, with mound, trench and pits as per instructions, for $\frac{1}{4}$ Sec. Cor.	
67.00	Ravine, N. 45° W.	
86.32	Intersect Tp. line at post, Cor. to Secs. 7 & 18 Soil; sandy, 3rd rate.	
40.00	N. on line bet. Secs. 7 & 8 Set charred stake, with mound, trench and pits; as per instructions, for $\frac{1}{4}$ Sec. Cor.	
80.00	Set charred stake, with mound, trench and pits as per instructions, for Cor. to Secs. 5, 6, 7 & 8 Var. 20° 45' E. Soil; quite sandy, 2nd rate.	
40.00	E. on random bet. Secs. 5 & 8 Set temp. $\frac{1}{4}$ Sec. Cor.	
80.44	Intersec Sec. line, 14 lks. S. of post Cor. to Secs. 4, 5, 8 & 9 S. 89° 54' W. on true line bet. Secs. 5 & 8	
40.22	Set charred stake, with mound, trench, pits as per instructions for $\frac{1}{4}$ Sec. Cor.	
56.50	Indian Trail, course N.	
80.44	Cor. to Secs. 5, 6, 7, & 8 Surface; uneven Soil; 2nd rate.	
40.00	S. 88° 10' W. on true line bet. Secs. 6 & 7 Set charred stake, with mound, trench and pits as per instructions, for $\frac{1}{4}$ Sec. Cor.	