

Subdivisional Lines of T. 4 N., R. 32 E., W.M.

Chains		Feet
	Land; gently rolling Grass good Soil; good 2nd rate.	
<hr/>		
	N. bet. Secs. 11 & 12, T. 4 N., R. 32 E. Var. 20° 30' E.	
40.00	Set $\frac{1}{4}$ Sec. post; drove charred stake, dug pits and raised mound as per instructions.	
80.00	Set post Cor. for Secs. 1, 2, 11 & 12; dug pits, drove charred stake & raised mound as per instructions.	
	Land; rolling Grass good Soil; 2nd rate.	
<hr/>		
	E. on random bet. Secs. 1 & 12, T. 4 N.R. 32 E.	
40.00	Set temp. $\frac{1}{4}$ Sec. post	
80.29	Intersect N. & S. line, 50 lks. S., post from which I run S. 89° 39' W. on true line	
40.14	Set $\frac{1}{4}$ Sec. post, drove charred stake, dug pits & raised mound as per instructions.	
80.29	To post Cor. Land; rolling Grass good Soil; 2nd rate.	
<hr/>		
	N. bet. Secs. 1 & 2, T. 4 N., R. 32 E. Var. 20° 30' E.	
40.00	Set $\frac{1}{4}$ Sec. post; drove charred stake, dug pits and raised mound as per instructions.	
71.00	Intersect First Standard Parallel, 40 lks. W. of post Cor. for Secs. 35 & 36, T 5 N R 32 E. Set Closing Cor. for Secs. 1 & 2; drove charred stake, dug pits and raised mound as per instructions. Land; gently rolling, good grass. Soil; 2nd rate.	