

Subdivisional Lines of T. 4 N., R. 32 E., W.M.

Chains		Feet
79.60	To post Cor. Land; rolling, grass good Soil; 2nd rate.	
<hr/> N. bet. Secs. 2 & 3, T. 4 N R 32 E		
Var. 20° 30' E.		
40.00	Set $\frac{1}{4}$ Sec. post; drove charred stake, dug pits and raised mound as per instructions	
71.00	Intersect First Standard Parallel, 30 lks. W. of post for Secs. 34 & 35, T 5 N R 32 E. Set Closing Cor. post for secs. 2 & 3; drove charred post, dug pits and raised mound as per instructions. Land; broken, grass good Soil; 2nd rate.	
<hr/> May 3rd, 1865		
N. bet. Secs. 33 & 34, T 4 N R 32 E		
Var. 20° 45' E		
15.00	To foot of hill	
40.00	Set $\frac{1}{4}$ Sec. post; drove charred stake, dug pits & raised mound as per instructions	
80.00	Set post Cor. for Secs. 27, 28, 33 & 34, in swale sloping gently to the E.; drove charred stake, dug pits and raised mound as per instructions. Land; rolling, grass good Soil; 2nd rate.	
<hr/> E. on random bet. Secs. 27 & 34, T 4 N R 32 E		
40.00	Set temp. $\frac{1}{4}$ Sec. post	
79.20	Intersect N. & S. line, 40 lks. N. of post from which I run N. 89° 43' W. on true line	
39.60	Set $\frac{1}{4}$ Sec. post on side hill sloping to the E.; drove charred stake, dug pits and raised mound as per instructions	
79.20	To post Cor.	