

Subdivisional Lines of T. 4 N., R. 32 E., W.M.

Chains		Feet
79.50	To post Cor. Land; rolling Grass good Soil; 2nd rate.	
<hr/>		
W. on random bet. Secs. 18 & 19, T. 4 N R 32 E		
40.00	Set temp. post	
80.40	Intersect N. & S. Tp. line at post, from which, E. on true line	
40.40	Set $\frac{1}{4}$ Sec. post in bottom of gully, course N.; drove charred stake, dug pits and raised mound as per instruc- tions.	
80.40	To post Cor. Land; broken Grass good Soil; 2nd rate.	
<hr/>		
N. bet. Secs. 17 & 18, T 4 N R 32 E		
Var. 20° 30' E.		
40.00	Set $\frac{1}{4}$ Sec. post; drove charred stake, dug pits and raised mound as per instructions.	
80.00	Set Post Cor. for Secs. 7, 8, 17 & 18; drove charred stake dug pits and raised mound as per instructions. Land; broken Good grass Soil; 2nd rate.	
<hr/>		
E. on random bet. Secs. 8 & 17, T 4 N R 32 E		
40.00	Set temp. $\frac{1}{4}$ Sec. post	
79.85	Intersect N. & S. line, 20 lks. S. of post, from which I run S. 89° 57' W. on true line	
39.92	Set $\frac{1}{4}$ Sec. post; drove charred stake; dug pits and raised mound as per instructions.	
79.85	To post Cor. Land; rolling	