

Subdivisional Lines of T. 4 N., R. 33 E., W.M.

Chains		Feet
80.00	Set post Cor. for Secs. 24, 27, 34 & 35. Drove charred stake, dug pits and raised mound as per instructions. Land; rolling, grass good Soil; good 2nd rate.	
April 27th 1865		
E. on random bet. Secs. 26 & 35, T. 4 N., R. 33 E.		
40.00	Set temp. $\frac{1}{4}$ Sec. post	
79.87	Intersect N. and S. line, 10 lks. S. of Post, from which Cor. I run, S. $89^{\circ} 55'$ W. on true line,	
39.93	Set $\frac{1}{4}$ Sec. post, drove charred stake, dug pits and raised mound as per instructions.	
79.87	To post cor. Land; gently rolling, grass good. Soil; 2nd rate.	
N. bet. Secs. 26 & 27, T. 4 N., R. 33 E.		
Var. 21° E.		
40.00	Set $\frac{1}{4}$ post, drove charred stake, dug pits and raised mound as per instructions.	
80.00	Set post, cor. for secs. 22, 23, 27 & 26. Drove charred stake. Land; rolling, grass good Soil; 2nd rate.	
E. on random line bet. Secs. 23 & 26, T. 4 N., R. 33 E.		
40.00	Set temp. $\frac{1}{4}$ Sec. post	
80.00	Intersect N. and S. line, 45 lks. S. of post, from which I run, S. $89^{\circ} 41'$ W. on true line	
40.00	Set $\frac{1}{4}$ Sec. post. Drove charred stake, dug pits and raised mounds as per instructions.	
80.00	To post cor. Land; rolling, good grass. Soil; 2nd rate.	