

Subdivisional Lines of T. 4 N., R.33 E., W.M.

Chains		Feet
	N. bet. Secs. 22 & 23, T. 4 N., R. 33 E.	
	Var. 21° E.	
40.00	Set $\frac{1}{4}$ Sec. post, drove charred stake, dug pits & raised mound as per instructions.	
80.00	Set post Cor. for secs. 14 & 15, 22 & 23, drove charred stake, dug pits and raised mound as per instructions. Land; rolling, grass good. Soil; 2nd rate.	
	E. on random bet. Secs. 14 & 23, T. 4 N., R. 33 E.	
40.00	Set temp. $\frac{1}{4}$ Sec. post.	
79.93	Intersect N. and S. line, 38 lks. S. of post, from which I run	
	S. 89° 44' W. on true line	
39.96	Set $\frac{1}{4}$ Sec. post. Drove charred stake, dug pits and raised mound as per instructions.	
79.93	To post cor. Land; rolling, grass good Soil; 2nd rate.	
	N. bet. Secs. 14 & 15, T. 4 N., R. 33 E.	
	Var. 21° E.	
35.00	A trail, course N.W.	
40.00	Set $\frac{1}{4}$ Sec. post, drove charred stake, dug pits and raised mound as per instructions.	
80.00	Set sec. post cor. for secs. 10, 11, 14 & 15. Drove charred stake, dug pits and raised mound as per instructions. Land; gently rolling, good grass. Soil; good 2nd rate.	
	E. on random bet. Secs. 11 & 14, T. 4 N., R. 33 E.	
40.00	Set $\frac{1}{4}$ sec. post temporarily;	
73.78	Intersect N. & S. line, 33 lks. S. of post from which I run S. 89° 46' W. on true line	
33.89	Set $\frac{1}{4}$ sec. cor. post. Drove charred stake, dug pits and	