

Subdivisional Lines of T. 4 N., R. 33 E., W.M.

Chains		Feet
	raised mound as per instructions.	
79.78	To post cor. Land; rolling, good grass Soil; good 2nd rate.	
<hr/>		
	N. bet. Secs. 10 & 11, T. 4 N., R. 33 E. Var. 21° E.	
40.00	Set $\frac{1}{4}$ Sec. post, drove charred stake, dug pits and raised mound as per instructions.	
80.00	Set post cor. for secs. 2, 3, 10 and 11. Drove charred stake, dug pits, and raised mound as per instructions. Land; rolling, good grass. Soil; good 2nd rate.	
April 28, 1868		
<hr/>		
	E. on random bet. Secs. 2 & 11, T. 4 N., R. 33 E.	
40.00	Set $\frac{1}{4}$ Sec. temp. Cor.	
79.85	Intersect N. and S. line, 60 lks. S. of post from which I run S. 89° 34' W. on true line	
39.92	Set $\frac{1}{4}$ Sec. post, drove charred post, dug pits, and raised mound as per instructions.	
79.85	To post cor. Land rolling, good grass. Soil; 2nd rate.	
<hr/>		
	N. bet. Secs. 3 & 2, T. 4 N., R. 33 E. Var. 21° E.	
40.00	Set $\frac{1}{4}$ Sec. post, drove charred stake, dug pits & raised mound as per instructions.	
60.40	Intersect Standard Line, 6.30 W. of Standard Cor. for Secs. 34 & 35, T. 5 N., R. 33 E. Set post for C. Cor. for Secs. 2 & 3, T. 4 N., R. 33 E., drove charred stake, dug pits & raised mound as per instructions. Land; rolling, grass good Soil; 2nd rate.	