

Subdivisional Lines of T. 4 N., R. 33 E., W.M.

Chains	April 29, 1865	Feet
	N. bet. Secs. 33 & 34, T. 4 N., R. 33 E.	
40.00	Set $\frac{1}{4}$ Sec. post, drove charred stake, dug pits & raised mound as per instructions.	
80.00	Set post Cor. for Secs. 27, 28, 33 & 34, drove charred stake, dug pits and raised mound as per instructions. Land; rolling, grass good. Soil; 2nd rate.	
<hr/> E. on random bet. Secs. 27 & 34, T. 4 N., R. 33 E.		
40.00	Set temp. $\frac{1}{4}$ Sec. post.	
79.25	Intersect N. and S. line, 40 lks. N. of post from which I run	
	N. 89° 43' W. on a true line	
39.62	Set $\frac{1}{4}$ Sec. post, drove charred stake, dug pits & raised mound as per instructions.	
79.25	To post cor. Land; rolling, grass good. Soil; 2nd rate.	
<hr/> N. bet. Secs. 27 & 28, T. 4 N., R. 33 E.		
	Var. 21° E.	
40.00	Set $\frac{1}{4}$ Sec. post, drove charred stake, dug pits & raised mound as per instructions.	
80.00	Set post cor. for Secs. 21 & 22, 27 & 28, drove charred stake, dug pits and raised mound as per instructions. Land; gently rolling, grass good Soil; 2nd rate.	
<hr/> E. on random bet. Secs. 22 & 27, T. 4 N., R. 33 E.		
40.00	Set temp. $\frac{1}{4}$ Sec. post.	
79.85	Intersect N. & S. line at post, from which I run W. on true line	
39.97	Set $\frac{1}{4}$ Sec. post, drove charred stake, dug pits & raised mound as per instructions.	
79.85	To post cor.	