

Subdivisional Lines of T. 4 N., R. 33 E., W.M.

Chains		Feet
	April 28, 1865	
	N. bet. Secs. 32 & 33, T. 4 N., R. 33 E.	
	Var. 21° E.	
40.00	Set $\frac{1}{4}$ Sec. post; drove charred stake, dug pits & raised mound as per instructions.	
80.00	Set post cor. for secs. 28, 29, 32 & 33; drove charred stake dug pits and raised mound as per instructions.	
	Land; rolling, grass good	
	Soil; 2nd rate.	
	<hr/>	
	E. on random bet. Secs. 28 & 33, T. 4 N., R. 33 E.	
40.00	Set temp. $\frac{1}{4}$ Sec. post	
79.45	Intersect N. and S. line, 15 lks. S. of post, from which I run	
	S. 89° 54' W. on true line	
39.72	Set $\frac{1}{4}$ Sec. post; drove charred stake, dug pits and raised mound as per instructions.	
79.45	To post Cor.	
	Land; rolling, grass good	
	Soil; 2nd rate.	
	<hr/>	
	N. bet. Secs. 28 & 29, T. 4 N., R. 33 E.	
	Var. 21° E.	
40.00	Set $\frac{1}{4}$ Sec. post; drove charred stake, dug pits and raised mound as per instructions.	
80.00	Set post Cor., for secs. 20, 21, 28 & 29. Drove charred stake dug pit and raised mound as per instructions.	
	Land; rolling, grass good.	
	Soil; 2nd rate.	
	<hr/>	
	E. on random bet. Secs. 21 & 28, T. 4 N., R. 33 E.	
40.00	Set temp. $\frac{1}{4}$ Sec. post	
79.15	Intersect N. and S. line, at post from which I run	
	W. on true line	
39.67	Set $\frac{1}{4}$ Sec. post; drove charred stake, dug pits and raised mound as per instructions.	