

Subdivisional Lines of T. 4 N., R. 33 E., W.M.

Chains		Feet
40.00	Set temp. $\frac{1}{4}$ Sec. post	
79.75	Intersect N. and S. line, 70 lks. N. of post from which I run N. $89^{\circ} 30'$ W. on true line	
39.82	Set $\frac{1}{4}$ Section post; drove charred stake, dug pits and raised mound as per instructions.	
79.75	To post cor. Land; rolling, grass, good. Soil; 2nd rate.	
N. bet. secs. 8 & 9, T. 4 N., R. 33 E.		
Var. 21° E.		
40.00	Set $\frac{1}{4}$ Sec. post cor; drove charred stake, dug pits and raised mound as per instructions.	
80.00	Set post cor. for secs. 4, 5, 8 & 9; drove charred stake dug pits and raised mound as per instructions. Land; broken, grass good Soil; 2nd rate.	
E. on random bet. Secs. 4 & 9, T. 4 N., R. 33 E.		
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
79.00	Intersect N. and S. line, 80 lks. N. of post, from which I run N. $89^{\circ} 26'$ W. on true line	
39.50	Set post cor., for $\frac{1}{4}$ Sec.; drove charred stake, dug pits and raised mound as per instructions.	
79.00	To post cor. Land; rolling Soil; 2nd rate. Grass, good.	
N. bet. secs. 4 & 5, T. 4 N., R. 33 E.		
Var. 21° E.		
40.00	Set $\frac{1}{4}$ sec. post; drove charred stake, dug pits and raised mound as per instructions.	