

Subdivisional Lines of T. 4 N., R. 34 E., W.M.

Chains		Feet
	N. bet. Secs. 2 & 3	
40.00	Set post cor. for $\frac{1}{4}$ Sec.; drove charred stake, dug pits and raised mound as per instructions.	
70.25	Intersect First Standard N., 6.71 chs. W. of Standard Cor. for Secs. 34 & 35, T. 5 N R 34 E.; at point of intersection set post cor. for sections. 2 & 3, drove charred stake, dug pits and raised mound as per instructions.	
	Land; rolling, good grass.	
	Soil; 2nd rate.	
	August 2nd 1866.	
	N. bet. Secs. 33 & 34	
40.00	Set post cor. for $\frac{1}{4}$ Sec.; drove charred stake, dug pits and raised mounds as per instructions.	
80.00	Set post cor. for secs. 27, 28, 33 & 34; drove charred stake, dug pits and raised mound as per instructions.	
	Land; rolling, good grass.	
	Soil; 2nd rate.	
	E. on random bet. Secs. 27 & 34	
	Var. 21° E	
40.00	Set temp. $\frac{1}{4}$ Sec. cor.	
79.73	Intersect N. and S. line, 29 lks. N. of post cor. N. 89° 48' W. on true line	
39.86	Set post cor. for $\frac{1}{4}$ Sec.; drove charred stake, dug pits and raised mound as per instruction.	
79.73	To post cor. Land; rolling, good grass. Soil; 2nd rate.	
	N. bet. Secs. 27 & 28	
2.50	Road, course E. and W.	
40.00	Set post cor. for $\frac{1}{4}$ Sec.; drove charred stake, dug pits and raised mound as per instructions.	
80.00	Set post cor. for secs. 21, 22, 27 & 28; drove charred	