

Subdivisional Lines of T. 4 N., R. 34 E., W.M.

Chains		Feet
	raised mound as per instructions.	
30.49	To post Cor. Land; broken, grass excellent Soil; 2nd rate.	
<hr/>		
	N. bet. Secs. 4 & 5	
40.00	Set post cor. for $\frac{1}{4}$ Sec.; drove charred stake, dug pits and raised mound as per instructions.	
70.30	Intersected 1st Standard N. 6.45 W. of Standard cor. for Secs. 32 & 33, T. 5 N., R. 34 E.; set post at point of intersection for Closing cor. for secs. 4 & 5; drove charred stake, dug pits and raised mound of earth as per instructions. Land; broken, grass good Soil; 2nd rate.	
August 4th, 1866		
<hr/>		
	N. bet. Secs. 31 & 32	
29.00	Road, course N.E. and S.W.	
40.00	Set post cor for $\frac{1}{4}$ Sec.; drove charred stake, dug pits and raised mound as per instructions.	
80.00	Set post cor. for secs. 29, 30, 31 & 32; drove charred stake, dug pits and raised mound as per instructions. Land; broken, grass excellent Soil; 2nd rate.	
<hr/>		
	E. on random bet. Secs. 29 & 32	
Var. 20° E.		
40.00	Set temp. $\frac{1}{4}$ Sec. post cor.	
79.52	Intersect N. and S. line, 56 lks. N. of post N. 89° 36' W. on true line	
39,76	Set post cor. for $\frac{1}{4}$ Sec.; drove charred stake, dug pits and raised mound as per instructions.	
79.52	To post cor. Land; rolling, good grass. Soil; 2nd rate.	