

Subdivisional Lines of T. 4 N., R. 34 E., W.M.

Chains		Feet
	and raised mound as per instructions.	
80.12	To post Cor. Land; rolling, grass excellent Soil; 2nd rate.	
<hr/>		
	N. bet. Secs. 19 & 20	
40.00	Set post cor. for $\frac{1}{4}$ Sec.; drove charred stake, dug pits and raised mound as per instructions.	
80.00	Set post cor. for Secs. 17, 18, 19 & 20; drove charred stake, dug pits and raised mound as per instructions. Land; rolling, grass excellent Soil; 2nd rate.	
<hr/>		
	E. on random bet. Secs. 17 & 20	
		Var. 21° E.
40.00	Set temp. $\frac{1}{4}$ Sec. post cor.	
79.65	Intersected N. and S. line, 28 lks. N. of post. N. 89° 48' W. on true line	
39.82	Set post cor. for $\frac{1}{4}$ Sec.; drove charred stake, dug pits and raised mound as per instructions.	
79.65	To post cor. Land; rolling, grass excellent, Soil; 2nd rate.	
<hr/>		
	W. on random bet. Secs. 18 & 19	
40.00	Set temp. $\frac{1}{4}$ Sec. post Cor.	
80.07	Intersected N. and S. line, 23 lks. S. of post S. 89° 50' E. on true line	
40.07	Set post Cor. for $\frac{1}{4}$ Sec.; drove charred stake, dug pits and raised mound as per instructions.	
80.07	To post Cor. Land; rolling, grass good. Soil; 2nd rate.	
<hr/>		
August 4, 1866		