

Subdivisional Lines of T. 4 N., R. 34 E., W.M.

Chains		Feet
20.70	Deposited charred stake, 12 ins. in the ground for 1/16 Sec. cor.; dug pits, 18 x 18 x 12 ins., N. and S. of stake, 5½ ft. dist., raised mound of earth, 1½ ft. high, 3½ ft. base over it and in N. pit drove stake 2 ft. long, 2 ins. sq. 12 ins. in the ground, marked 1/16 S. on W. face.	
30.00	Wagon road, E. and W.	
40.70	Set post, 3 ft. long, 3 ins. sq., 24 ins. in the ground, for ¼ Sec. Cor., marked ¼ S. on W. face, dug pits 18 x 18 x 12 ins. N. and S. of post, 5½ ft. dist, raised mound of earth, 1½ ft. high, 3½ ft. base around it	
49.70	Wire fence, and enter field	
60.70	Set post, 3 ft. long, 3 ins. sq., 24 ins. in the ground for 1/16 S. on W. face, dug pits, 18 x 18 x 12 ins. N. and S. of Cor. 5½ ft. dist., raised mound of earth, 1½ ft. high 3½ ft. base around post.	
80.70	Cor. to Secs. 25 & 26, 35 & 36. Land; rolling Soil; 1st rate. No timber, can all be cultivated.	
	Commencing at Cor. to Secs. 26, 27, 34 & 35, which is a stone buried in the ground, 12 ins. deep in old mound, old pits in each Sec. 5½ ft. dist. thence, I run E. on random line bet. 26 & 35 Var. 19¼° E.	
40.00	Set temp. ¼ Sec. Cor. and at	
79.35	Intersect E. Bdy. at cor. to Secs. 25, 26, 35 & 36, thence W. on true line Var. same.	
39.67	Set post, 3 ft. long, 3 ins. sq., 24 ins. in the ground for ¼ Sec. Cor., marked ¼ S. on N. face, dug pits 18 x 18 x 12 ins. E. and W. of post, 5½ ft. dist, raised mound of earth, 1½ ft. high, 3½ ft. base around it.	
40.90	Leave field, S.W.	
43.25	O.R. & N., R.R., S.W.	