

Subdivisional Lines of T. 4 N R 35 E., W.M.

Chains		Feet
	N. bet. Secs. 25 & 26	
10.00	Summit of ridge	
38.75	Small spring branch, course N.W.	
40.00	Set post Cor. for $\frac{1}{4}$ Sec. on hillside, facing the W.; drove charred stake, dug pits and raised mound as per instructions.	
77.00	Small spring branch, course W.	
80.00	Set post Cor. for Secs. 23, 24, 25 & 26, on hillside, facing the S.W.; drove charred stake, dug pits and raised mound as per instructions.	
	Land; broken, good grass	
	Soil; 2nd rate.	
<hr/>		
	E. on random bet. Secs. 24 & 25	
		Var. 21° E.
40.00	Set temp. $\frac{1}{4}$ Sec. post Cor.	
80.20	Intersected N. & S. line, 33 lks. S. of Cor. S. 89° 46' W. on true line	
40.10	Set post Cor. for $\frac{1}{4}$ Sec.; drove charred stake, dug pits and raised mound as per instructions. On summit of Divide, bet. Dry Creek and Pine Creek.	
80.20	To post Cor. Land; broken Soil; 2nd rate.	
<hr/>		
	N. bet. Secs. 23 & 24	
40.00	Set post Cor. for $\frac{1}{4}$ Sec.; drove charred stake, dug pits and raised mound as per instructions.	
80.00	Set post Cor. for Secs. 13, 14, 23 & 24; drove charred stake, dug pits and raised mound as per instructions. Land; broken, good grass Soil; 2nd rate.	
<hr/>		
	E. on random bet. Secs. 13 & 24	
		Var. 21° E.
40.00	Set temp. $\frac{1}{4}$ Sec. post Cor.	