

## Subdivisional Lines of T. 4 N., R. 35 E., W.M.

Chains		Feet
	N. bet. Secs. 11 & 12	
40.00	Set post Cor.; drove charred stake, dug pits and raised mound as per instructions.	
80.00	Set post Cor. for Secs. 1, 2, 11 & 12, in gulch, course N.; drove charred stake, dug pits and raised mound as per instructions.	
	Land; broken, good grass	
	Soil; 2nd rate.	
<hr/>		
	E. on random bet. Secs. 1 & 12	
		Var. 21° E.
40.00	Set temp. $\frac{1}{4}$ Sec. post Cor.	
80.23	Intersected N. & S. line, 10 lks. S. of post Cor.	
	S. 89° 51' W. on true line	
40.11	Set post Cor. for $\frac{1}{4}$ Sec.; drove charred stake, and raised stone mound as per instructions.	
60.25	E. Branch of Dry Creek, 5 lks. wide, course N.W.	
80.23	To post Cor.	
	Land; broken, good grass	
	Soil; 2nd rate.	
<hr/>		
	N. bet. Secs. 1 & 2	
13.60	Dry Creek, course N.W., 5 lks. wide	
40.00	Set post Cor. for $\frac{1}{4}$ Sec. on hillside facing the S.; drove charred stake, dug pits and raised mound as per instructions.	
63.10	Intersected 1st Standard Parallel N., 8.30 lks. W. of standard Cor. for Secs. 35 & 36, T 5 N R 35 E. At point of intersection, set Closing Cor. for Secs. 1 & 2; drove charred stake, dug pits and raised mound as per instructions.	
	Land; broken, good grass	
	Soil; 2nd rate.	
<hr/>		
	N. bet. Secs. 34 & 35	
40.00	Set post Cor. for $\frac{1}{4}$ Sec. on land that slopes to the N.;	