

Subdivisional Lines of T. 4 N., R. 35 E., W.M.

Chains		Feet
	At point of intersection set post Closing Cor. for Secs. 3 & 4, drove charred stake, dug pits and raised mound as per instructions. Land; rolling, good grass Soil; 2nd rate.	
	<hr/>	
	N. bet. Secs. 32 & 33	
22.50	Wild Horse Creek, 4 lks. wide, course N.W. and enter field.	
30.75	Leave field	
40.00	Set $\frac{1}{4}$ Sec. post Cor.; drove charred stake, dug pits and raised mound as per instructions.	
80.00	Set post Cor. for Secs. 28, 29, 32 & 33; drove charred stake, dug pits and raised mound as per instructions. Land; rolling, good grass Soil; good 2nd rate.	
	<hr/>	
	E. on random bet. Secs. 28 & 33	
		Var. 21° 30' E.
40.00	Set temp. $\frac{1}{4}$ Sec. post Cor.	
80.50	Intersected N. and S. line, 10 lks. S. of post. S. 89° 50' W. on true line	
40.25	Set $\frac{1}{4}$ Sec. post Cor.; drove charred stake, dug pits and raised mound as per instructions.	
49.50	Enter field, course of fence, N.W. and S.E.	
59.50	Leave field	
80.50	To post Cor. Land; rolling, good grass Soil; good 2nd rate.	
	<hr/>	
	N. bet. Secs. 28 & 29	
40.00	Set $\frac{1}{4}$ Sec. Cor. post; drove charred stake, dug pits and raised mound as per instructions.	
80.100	Set post Cor. for Secs. 20, 21, 28 & 29; drove charred stake dug pits and raised mound as per instructions. Land; rolling, good grass Soil; good 2nd rate.	