

Subdivisional Lines of T. 4 N R 35 E., W.M.

Chains		Feet
	Land; broken, good grass Soil; good 2nd rate. August 23rd 1866.	
	<hr/>	
	E. on random bet. secs. 9 & 16 Var. 21° E.	
40.00	Set temp. $\frac{1}{4}$ Sec. post Cor.	
80.12	Intersected N. & S. line, 39 lks. S. of post Cor. S. 89° 43' W. on true line	
40.06	Set post Cor. for $\frac{1}{4}$ Sec.; drove charred stake, dug pits and raised mound as per instructions.	
80.12	To post Cor. Land; rolling, good grass Soil; 2nd rate.	
	<hr/>	
	N. bet. Secs. 8 & 9	
40.00	Set post Cor. for $\frac{1}{4}$ Sec.; drove charred stake, dug pits and raised mound as per instructions.	
80.00	Set post Cor. for Secs. 4, 5, 8 & 9; drove charred stake, dug pits and raised mound as per instructions. Land; good 2nd rate.	
	<hr/>	
	E. on random bet. Secs. 4 & 9 Var. 20° 30' E.	
40.00	Set temp. $\frac{1}{4}$ Sec. post Cor.	
80.09	Intersected N. & S. line, 43 lks. S. of post Cor. S. 89° 42' W. on true line	
40.04	Set post Cor. for $\frac{1}{4}$ Sec.; drove charred stake, dug pits, raised stone mound as per instructions.	
59.00	Pine Creek, 10 lks. wide, course N.W.	
80.09	To post Cor. Land; broken, good grass Soil; 2nd rate.	
	<hr/>	
	N. bet. 4 & 5	
12.10	Pine Creek, 10 lks. wide, course N.W.	