

Subdivisional Lines of T. 4 N., R. 35 E., W.M.

Chains		Feet
37.15	Set post Cor. for $\frac{1}{4}$ Sec.; drove charred stake, dug pits and raised mound as per instructions.	
77.15	To post Cor. Land; rolling, good grass Soil; 2nd rate.	
N. bet. Secs. 29 & 30		
40.00	Set post Cor. for $\frac{1}{4}$ Secs.; drove charred stake, dug pits and raised mound as per instructions.	
50.00	Wild Horse Creek, 10 lks. wide, course N.W.	
62.50	Enter field, course of fence, N.E. & S.W.	
68.40	Leave field, course of fence N.W. & S.E.	
80.00	Set post Cor. for Secs. 19, 20, 29 & 30; drove charred stake dug pits and raised mound as per instructions.	
	Land; rolling, good grass	
	Soil; good 2nd rate.	
E. on random bet. Secs. 20 & 29		
		Var. 21° E.
40.00	Set temp. $\frac{1}{4}$ Sec. post Cor.	
79.86	Intersected N. & S. line, 35 lks. N. of post Cor. N. 89° 45' W. on true line	
39.93	Set post Cor. for $\frac{1}{4}$ Sec.; drove charred stake, dug pits and raised mound as per instructions.	
79.86	To post Cor. Land; rolling, good grass Soil; good 2nd rate.	
		August 24, 1866
W. on random bet. Secs. 19 & 30		
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
77.23	Intersected N. & S. line, 15 lks. S. of post Cor. S. 89° 54' E. on true line	
37.23	Set post Cor. for $\frac{1}{4}$ Sec.; drove charred stake, dug pits and raised mound as per instructions.	
59.00	Wild Horse Creek, 8 lks. wide, course N.W. and enter field.	