

Subdivisional Lines of T. 4 N R 35 E., W.M.

Chains	
69.14	Leave field, course of fence, N.W. and S.E.
77.23	To post Cor.
	Land; rolling, excellent grass
	Soil; good 2nd rate.
<hr/>	
	N. bet. Secs. 19 & 20
40.00	Set post Cor. for $\frac{1}{4}$ Sec.; drove charred stake, dug pits and raised mound as per instructions.
69.00	Road, course N.E.
80.00	Set post Cor. for Secs. 17, 18, 19 & 20; drove charred stake, dug pits and raised mound as per instructions.
	Land; gently rolling
	Good grass
	Soil; 2nd rate.
<hr/>	
	E. on random bet. Secs. 17 & 20
	Var. 21° E.
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.
79.91	Intersected N. & S. line, 43 lks. S. of post Cor.
	S. 89° 42' W. on true line
39.96	Set post Cor. for $\frac{1}{4}$ Sec.; drove charred stake, dug pits and raised mound as per instructions.
79.91	To post Cor.
	Land; gently rolling
	Soil; 2nd rate.
<hr/>	
	W. on random bet. Secs. 18 & 19
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.
77.10	Intersected N. & S. line, 20 lks. N. of post Cor.
	N. 89° 51' E. on true line
37.10	Set post Cor. for $\frac{1}{4}$ Sec.; drove charred stake, dug pits and raised mound as per instructions.
77.10	To post Cor.
	Land; gently rolling
	Soil; 2nd rate.