

## Subdivisional Lines of T. 4 N., R. 35 E., W.M.

Chains		Feet
	<p>instructions.</p> <p>Land; broken</p> <p>Soil; 2nd rate.</p>	
	<u>GENERAL DESCRIPTION</u>	
	<p>All the lands in this Tp. are well adapted to stock raising and much of the lands in the Southern and Eastern portions are good for agricultural purposes.</p> <p>A considerable settlement has already been made.</p> <p style="text-align: right;">August 25th, 1866</p>	
	<p>Resurvey of Subdivisional Lines of T. 4 N R 35 E., W.M. As surveyed by Z.F. Moody, U.S. Deputy Surveyor Under Contract No. 164 Dated Oct. 4, 1871</p>	
	N. bet. Secs. 32 & 33	
23.00	Wild Horse Creek, the Northern Bdy. of the Reservation.	
	N. bet. Secs. 31 & 32	
40.00	Set post and made mound of earth for $\frac{1}{4}$ Sec. Cor.	
80.00	Set post and made mound of earth for Cor. to Secs. 31, 32, 29 & 30.	
	Land; rolling	
	Soil; good	
	Good Grass.	
	E. bet. Secs. 29 & 32	
	Var. 20° 45' E.	
40.00	Set post and made mound of stone for $\frac{1}{4}$ Sec. Cor.	
50.60	To Wild Horse Creek, the bdy of the Reservation.	
	Land; rolling	
	Good grass.	
	W. on random bet. Secs. 30 & 31	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
78.00	Intersected N. & S. line, 14 lks. N. of Cor.	
	N. 89° 54' E. on true line	
38.00	Set post and made mound of earth for $\frac{1}{4}$ Sec. Cor.	