

Resurvey of Subdivisional Lines of T. 4 N., R. 35 E., W.M.

Chains		Feet
30.68	<p>Cor. to Secs. 29, 30, 31 & 32.</p> <p>Land; mostly level</p> <p>Soil; 1st rate.</p> <p>Cultivated.</p>	
	<p>W. on random bet. Secs. 30 & 31</p> <p style="text-align: right;">Var. 20° E.</p>	
75.90	<p>Set temp. Cor., at 20, 40 & 60 chs. and at</p> <p>Intersect W. Bdy. Tp. 32 lks. S. of Cor. to Secs. 30, 31, 25 & 36</p> <p>Thence S. 89° 46' E. on true line bet. Secs. 30 & 31</p> <p style="text-align: right;">Var. 19 3/4° E.</p>	
14.40	<p>Wagon road, N. & S.</p>	
15.90	<p>Deposited charred stake, 12 ins. in the ground for 1/16 Sec. Cor., dug pits, 18 x 18 x 12 ins. E. & W. of stake, 5 1/2 ft. dist., raised mound of earth, 1 1/2 ft. high, 3 1/2 ft. base over it and in E. pit, drove stake 2 ft. long, 2 ins. sq., 12 ins. in the ground, marked 1/16 S. on N. face.</p>	
35.90	<p>Deposited charred stake, 12 ins. in the ground for 1/4 Sec. Cor., dug pits, 18 x 18 x 12 ins. E. & W. of stake, 5 1/2 ft. dist., raised mound of earth 1 1/2 ft. high, 3 1/2 ft. base over it and in E. pit, drove stake, 2 ft. long, 2 ins. sq., 12 ins. in the ground marked 1/4 S. on N. face</p>	
53.40	<p>Wagon road in land, N. & S.</p>	
55.90	<p>Deposited charred stake, 12 ins. in the ground for 1/16 Sec. Cor., dug pits, 18 x 18 x 12 ins. E. & W. of stake, 5 1/2 ft. dist., raised mound of earth, 1 1/2 ft. high, 3 1/2 ft. base over it and in E. pit; drove charred stake, 2 ft. long, 2 ins. sq., 12 ins. in the ground, marked 1/16 S. on N. face.</p>	
75.90	<p>Cor. to Secs. 29, 30, 25 & 36</p> <p>Land; level or slightly rolling</p> <p>Soil; 1st rate</p> <p>All cultivated.</p>	