

Resurvey of Subdivisional Lines of T. 4 N., R. 35 E., W.M.

| Chains | | Feet |
|---|---|------|
| 40.00 | No sign of old $\frac{1}{4}$ Sec. Cor. and owing to the land being cultivated and outside reservation I did not establish one. | |
| 57.00 | Set post, 4 ft. long, 4 ins. sq., 24 ins. in the ground on S. bank of the Wild Horse Creek, for Meander Cor. to fractional Secs. 32 & 33, marked U.R.M.C. with T 4 N. on S., R 35 E., S. 33 on E. and S. 32 on W. faces, dug pits, 3 ft. sq., 1 ft. deep 8 lks. S. of post and raised mound of earth, 2 ft. high 4 ft. base around post. | |
| 60.00 | Deposited charred stake, 12 ins. in the ground for $\frac{1}{16}$ Sec. Cor., dug pits, 18 x 18 x 12 ins. N. & S. of stake, $5\frac{1}{2}$ ft. dist. raised mound of earth, $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it, and in N. pit; drove stake, 2 ft. long, 2 ins. sq., 12 ins. in the ground, marked $\frac{1}{16}$ S. on W. face. | |
| 79.50 | Wagon road and lane, E. & W. | |
| 79.80 | Intersect S. Bdy., Tp. 34 lks. W. of Cor. to Secs. 4 & 5, T 3 N., R. 35 E., and set post 4 ft. long, 4 ins. sq., 24 ins. in the ground, for closing Cor. to Secs. 32 & 33, marked C. C., T 4 N, R 35 E. on N., S. 33 on E. & S. 32 on W. faces, with 4 notches on E. and 2 notches on W. faces, dug pits, 18 x 18 x 12 ins. N.E. & W of stake, $5\frac{1}{2}$ ft. dist. and raised mound of earth, 2 ft. high, $4\frac{1}{2}$ ft. base around it. | |
| | Land; mostly level | |
| | Soil; 1st rate. | |
| | Mostly cultivated | |
| | Aug. 17th, 1887. | |
| <u>General Description</u> | | |
| This Tp. is rolling. The soil is a rich loam, sandy on higher ground and very black and rich along the Wild Horse, producing fine grain, fruit and vegetables. Scattering Cottonwoode along the Wild Horse, with thick thorn and Willow underbrush. | | |