

Sub-subdivisions of T 4 N., R 35 E., W.M.

Chains		Feet
80.48	<p>Sec. Cor., dug pits, 18 x 18 x 12 ins. E. & W. of stake, 5½ ft. dist., raised mound of earth, 1½ ft. high, 3½ ft. base over it and in E. pit; drove stake, 2 ft. long, 2 ins. sq., 12 ins. in the ground, marked 1/16 S. on N. face.</p> <p>To point of beginning</p> <p>Land; gently rolling</p> <p>Soil; 1st rate.</p> <p>Mostly cultivated</p>	0
20.13	<p>S. 89° 32' E. on true line through center of Sec. 32</p> <p style="text-align: right;">Var. 20° E. and</p> <p>Commencing at ¼ Sec. Cor., running parallel with the N. Bdy. of Sec. as the E. Bdy. of this Sec. is outside of the deminished reserve and by comparing the N. & S. Bdy. of this Sec. I find the length of this line will be 80.54 Chs., therefore at</p> <p>Deposited charred stake, 12 ins. in the ground for ¼ Sec. Cor., dug pits, 18 x 18 x 12 ins. E. & W. of stake, 5½ ft. dist.; raised mound of earth, 1½ ft. high 3½ ft. base over it and in E. pit, drove stake 2 ft. long, 2 ins. sq., 12 ins. in the ground, marked: 1/16 S. on N. face.</p>	0
40.27	<p>Deposited charred stake, 12 ins. in the ground for ¼ Sec. Cor., dug pits, 18 x 18 x 12 ins. E. & W. of stake, 5½ ft. dist.; raised mound of earth, 1½ ft. high, 3½ ft. base over it, and in E. pit; drove stake 2 ft. long 2 ins. sq., 12 ins. in the ground: marked ¼ S. on N. face.</p>	0
60.40	<p>Deposited charred stake, 12 ins. in the ground for 1/16 Sec. Cor., dug pits 18 x 18 x 12 ins. E. & W. of stake, 5½ ft. dist., raised mound of earth, 1½ ft. high, 3½ ft. base over it and in E. pit, drove stake, 2 ft. long, 2 ins. sq., 12 ins. in the ground: marked 1/16 S. on N. face.</p> <p>Line discontinued at this point</p> <p>Land; rolling</p> <p>All cultivated.</p>	0