

Exterior Bdy. of T. 4 N., R. 36 E., W.M. (N. Bdy.)  
 As surveyed by Wm H. Odell, and Lewis, U.S. Deputy Surveyors.  
 Under Contract No. 110, Dated Feb. 7, 1865

Chains		Feet
	May 13th, 1865.	
	E. on S. Bdy. of Sec. 31, T. 5 N., R. 36 E.	
	Var. 21° E.	
38.00	To fence runing N.E. and S.W.	
40.00	Set $\frac{1}{4}$ post side of hill, sloping toward Chouse Creek, N.E.	
	Drove charred stake, dug pits and raised mound as per instructions.	
40.00	To ditch, fence, course S.E.	
52.00	Chouse Creek, course N.W.	
.40	Wide	
57.00	Cross ditch, fence	
75.00	Crossed trail, course S.E.	
80.00	Set Standard Cor. for Secs. 31 & 32, in T 5 N, R 36 E. On side hill sloping to the W.	
	Soil; good 2nd rate.	
	Land; rolling, grass good.	
	First Standard Parallel E. on S. Bdy. of Sec. 32, T 5 N R 36 E.	
	Var. 21° E.	
40.00	Set $\frac{1}{4}$ Sec. post on side hill; drove charred stake, dug pits and raised mound as per instructions.	
80.00	Set Standard Cor. for Secs. 32 & 33, T 5 N., R. 36 E., on side hill, sloping to the N.W.; dug pit & raised mound as per instructions.	
	Land; broken	
	Soil; 2nd rate.	
	Grass good,	
	E. on S. Bdy. of Sec. 33,	
	Var. 21° E.	
40.00	Set post Standard Cor. for $\frac{1}{4}$ Sec. on side hill sloping to N.E.; drove charred stake, dug pits and raised mound as per instructions.	
	N. bet. T. 4 & 5 N., R. 36 E.	
80.00	Set Standard Cor. for Secs. 33 & 34, in T 5 N., R. 36 E., near top of high spur sloping to the N.W.; drove charred post, dug pits and raised mound as per instructions.	