

Exterior Bdy. of T. 4 N., R. 36 E., W.M. (N.Bdy.)

| Chains | | Feet |
|--------|---|------|
| | Land; broken Soil; 2nd rate. Grass good. | |
| | E. on S. Bdy. of Sec. 34, Var. 21° E. | |
| 36.50 | To fine spring | |
| 40.00 | Set post Standard Cor. for $\frac{1}{4}$ Sec. on steep hill side sloping S.W.; drove charred stake, dug pits, raised mound as per instructions. | |
| 71.00 | Bottom of ravine | |
| 80.00 | Set Standard Cor. for Secs. 34 & 35, T 5 N R 36 E. on side hill sloping to S.W.; line passes across the spur of mountains coursing to the N.W.; drove charred stake, dug pits and raised mound as per instructions. | |
| | E. on S. Bdy. of Sec. 35. Var. 23° 30' E. | |
| 40.00 | Set post Standard Cor. for $\frac{1}{4}$ Sec. in flat on top of spur, about 800 ft. high; drove charred stake, dug pits and raised mound as per instructions. | |
| 57.00 | Crossed road, course N.W. | |
| 76.50 | Crossed same road. | |
| 80.00 | Set Standard Cor. for Secs. 35 and 36, T 5 N., R. 36 E.; drove charred stake, and made stone mound as per instructions. | |
| | Land; very broken Grass; 2nd rate. Soil; mostly 2nd rate. | |
| | E. on S. Bdy. of Sec. 36, Var. 21° 30' E. | |
| 32.00 | Crossed Linkton's Road, course N.W. | |
| 40.00 | Set post Standard Cor. for $\frac{1}{4}$ Sec.; drove charred stake, dug pits and raised mound on steep hill side sloping to the N. to Walla Walla River, south fork. | |