

Subdivisional Lines of T. 4 N R 36 E., W.M.

Chains		Feet
	E. on random bet. Secs. 24 & 25 Var. 15° 30' E.	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
79.87	Intersect N. and S. line, 41 lks. S. of post Cor. S. 89° 43' W. on true line	
39.93	Set basalt stone, 5 x 10 x 15 for $\frac{1}{4}$ Sec. Cor. on hillside facing the W.	
67.50	Bottom of ravine, course N.	
79.87	To post Cor. Land; broken, good grass Soil; on E. $\frac{1}{2}$, 2nd rate. W. $\frac{1}{2}$ stony. Sept. 26th, 1866.	
	N. bet. Secs. 23 & 24	
40.00	Set post Cor. for $\frac{1}{4}$ Sec. on steep hillside in edge of timber, from which A Larch, 18 ins. diam. brs. 35° W., 18 lks. A Larch, 20 ins. diam. brs. N. 10° E., 15 lks.	
41.00	Dry creek, very little water, course N.W.	
80.00	Set post Cor. for Secs. 13, 14, 23 & 24, on steep hillside facing the W.; drove charred stake and raised stone mound as per instructions. Land; broken Soil; stony.	
	E. on random bet. Secs. 13 & 24 Var. 20° E.	
40.00	Set temp. $\frac{1}{4}$ Sec. post Cor.	
80.09	Intersected N. and S. line, 38 lks. S. of post Cor. S. 89° 44' W. on true line	
40.04	Set post Cor. for $\frac{1}{4}$ Sec. from which A Fir, 18 ins. diam. brs. N. 15° E., 7 lks. A Larch, 6 ins. diam. brs. S. 88° E., 8 lks.	
80.09	To post Cor. Land; broken, good grass Soil; 2nd rate.	