

Subdivisional Lines of T. 4 N., R. 36 E., W.M.

Chains	Feet
	N. bet. Secs. 22 & 23
40.00	Set post Cor. for $\frac{1}{4}$ Sec., from which A Pine, 20 ins. diam. brs. S. 362 No other tree, dug pits and raised mound as per instructions.
80.00	Set post Cor. for Secs. 14, 15, 22 & 23; drove charred stake, and raised stone mound as per instructions. Land; gently rolling Good grass Soil; 2nd rate.
	E. on random bet. Secs. 14 & 23 Var. 19° E.
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.
80.64	Intersected N. and S. line, 51 lks. N. of post Cor. N. 89° 44' W. on true line
25.25	Bottom of ravine, course N.
40.32	Set post Cor. for $\frac{1}{4}$ Sec.; drove charred stake, dug & raised stone mound as per instructions.
47.00	Summit of ridge
62.50	Bottom of ravine, course N.
80.64	To post Cor. Land; broken, good grass Soil; stony.
	N. bet. Secs. 14 & 15
40.00	Set basalt stone, 9 x 11 x 12 for $\frac{1}{4}$ Sec. Cor. on steep hillside facing the N.
42.00	Dry Creek, 5 lks. wide, course W.
80.00	Set post Cor. for Secs. 10, 11, 14 & 15; drove charred stake and raised mound as per instructions. Land; broken and rocky.
	Oct. 3rd, 1866 E. on random bet. Secs. 14 & 15.
40.00	Set temp. $\frac{1}{4}$ Sec. Cor. Var. 19° E.