

Subdivisional Lines of T. 4 N., R. 36 E., W.M.

Chains		Feet
81.61	Intersected N. & S. line, 72 lks. N. of post Cor. N. 89° 29' W. on true line	
40.30	Set basalt stone, 9 x 10 x 15 for $\frac{1}{4}$ Sec. Cor.	
76.00	Road, course N.W.	
80.61	To post Cor. Land; gently descending Grass good. Soil; 2nd rate.	
N. bet. Secs. 10 & 11		
2.50	Road, course N.W.	
40.00	Set basalt stone, 4 x 12 x 16, for $\frac{1}{4}$ Sec. Cor. on hillside facing the W.	
80.00	Set post Cor. fo Secs. 2, 3, 10 and 11; drove charred stake, dug pits and raised mound as per instructions. Land; broken, good grass. Soil; 2nd rate.	
E. on random bet. Secs. 2 & 11		
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	Var. 20° E.
80.66	Intersected N. and S. line, 49 lks. N. of post Cor. N. 89° 39' W. on true line	
35.00	Bottom of ravine, course N.	
40.33	Made cor. on basalt boulder, 36 x 42 and as deep as may be, on steep hillside, facing the E.	
80.66	To post Cor. Land; broken, good grass Soil; 2nd rate.	
N. bet. Secs. 2 & 3		
20.75	Creek, 5 lks. wide, course W.	
40.00	Set basalt stone, 7 x 9 x 14, Cor. for $\frac{1}{4}$ Sec.	
68.50	Intersected 1st Standard Parallel N. 12.73 W.of Cor. for Secs. 34 & 35, T 5 N R 36 E. Set post Closing Cor. for Secs. 2 & 3; drove charred stake	