

## Subdivisional Lines of T. 4 N., R. 36 E., W.M.

Chains		Feet
80.00	Set post Cor. for Secs. 21, 22, 27 & 28, from which A Pine, 36 ins. diam. brs. S. 20° E., 60 lks. A Pine, 30 ins. diam. brs. S. 68° W., 139 lks. A Pine, 24 ins. diam. brs. N. 30° W., 129 lks. A Pine, 4 ins. diam. brs. N. 55° E., 17 lks.	
	Land; gently rolling, good grass. Timber; pine, well suited making lumber.	
	E. on random bet. Secs. 22 & 27 <div style="text-align: right;">Var. 20° 30' E.</div>	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
79.58	Intersected N. and S. line, 43 lks. N. of Post Cor. N. 89° 42' W. on true line	
39.79	Set post Cor. for $\frac{1}{4}$ Sec; drove charred stake, and raised stone mound as per instructions.	
44.50	Bottom of ravine, course N.	
79.58	To post Cor. Land; broken, good grass Timber; open, Pine Soil; 2nd rate.	
	N. bet. Secs. 21 & 22	
40.00	Set post Cor. for $\frac{1}{4}$ Sec.; drove charred stake, dug pits and raised mound as per instructions.	
30.00	Set post Cor. for Secs. 15, 16, 21 & 22, from which A Pine, 20 ins. diam. brs. N. 136 lks. A Pine, 20 ins. diam. brs. S. 85° W. 310 lks. A Larch, 18 ins. diam. brs. N. 80° W., 236 lks. No tree near in Sec. 22.	
	Land; broken Soil; 2nd rate.	
	E. on random bet. Secs. 15 & 22 <div style="text-align: right;">Var. 20° E.</div>	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
79.65	Intersected N. and S. line, 40 lks. N. of post Cor.	