

Subdivisional Lines of T. 4 N., R. 36 E., W.M.

Chains		Feet
	Land; broken, good grass Soil; 2nd rate.	
	<hr/>	
	E. on random bet. Secs. 28 & 33 Var. 20° 30' E.	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
80.15	Intersected N. and S. line, 44 lks. S. of post Cor. S. 89° 42' W. on a true line	
40.07	Set post Cor. for $\frac{1}{4}$ Sec. from which A fir, 10 ins. diam. brs. S. 20° W., 46 lks. A pine, 20 ins. diam. brs. N. 33° W., 46 ⁴¹ lks.	
75.00	Cross Cor. of ploughed land to the S.	
80.15	To post Cor. Land; broken, good grass Soil; 2nd rate.	
	<hr/>	
	N. bet. Secs. 28 & 29	
40.00	Set post Cor. for $\frac{1}{4}$ Sec. from which A pine, 36 ins. diam. brs. S. 80° W., 90 lks A pine, 7 ins. diam. brs. S. 70° E., 94 lks.	
80.00	Set post Cor. for Secs. 20, 21, 28 & 29, from which A pine, 12 ins. diam. brs. S. 5° W., 36 lks. A pine, 15 ins. diam. brs. S. 30° E., 63 lks. No trees near in Secs. 20 & 21; dug pits and raised mound as per instructions. Land; rolling, good grass. Soil; 2nd rate.	
	<hr/>	
	E. on random bet. Secs. 21 & 28 Var. 20° E.	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
80.37	Intersected N. and S. line, 56 lks. S. of post Cor. S. 89° 36' W. on true line.	
40.18	Set post Cor. for $\frac{1}{4}$ Sec., from which A pine, 12 ins. diam. brs. N. 40° E., 155 lks. A pine, 20 ins. diam. brs. S. 8° W., 125 lks.	