

## Subdivisional Lines of T. 4 N., R. 36 E., W.M.

Chains		Feet
75.50	Road to Steam Saw mill, course N.W.	
80.37	To post Cor.	
	Land; rolling, good grass	
	Soil; 2nd rate.	
	N. bet. Secs. 20 & 21	
40.00	Set post Cor. for $\frac{1}{4}$ Sec.; in prairie; drove charred stake, dug pits and raised mound as per instructions.	
80.00	Set post Cor. for Secs. 16, 17, 20 & 21; drove charred stake, dug pits and raised mound as per instructions.	
	Land; broken, good grass	
	Soil; 2nd rate.	
	E. on random bet. Secs. 16 & 21	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
80.29	Intersected N. and S. line, 85 lks. S. of post Cor.	
15.75	Bottom of ravine, course N.	
40.14	Set post Cor. for $\frac{1}{4}$ Sec.; drove charred stake, and raised stone mound as per instructions.	
80.29	To post Cor.	
	Land; broken, good grass	
	Soil; 2nd rate.	
	N. bet. Secs. 16 & 17	
40.00	Set basalt stone, 8 x 10 x 14 for $\frac{1}{4}$ Sec. Cor.	
55.00	Dry Creek, 4 lks. wide, course N.W.	
80.00	Set post Cor. for Secs. 8, 9, 16 & 17, on hillside facing the S.W.; drove charred stake, dug pits and raised mound as per instructions.	
	Land; broken, good grass	
	Soil; 2nd rate.	
	E. on random bet. Secs. 9 & 16	
		Var. 21° E.