

## Subdivisional Lines of T. 4 N., R. 36 E., W.M.

Chains		Feet
	N. bet. Secs. 19 & 20	
15.00	Bottom of ravine, course N.W.	
40.00	Set basalt stone, 6 x 10 x 14, cor. for $\frac{1}{4}$ Sec. Cor.	
80.00	Set post Cor. for Secs. 17, 18, 19 & 20; deposited marked stone and raised stone mound as per instructions.	
	Land; broken, good grass	
	Soil; 2nd rate.	
	Oct. 8th, 1866.	
	E. on random bet. Secs. 17 & 20	
	Var. 21° E.	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
79.91	Intersected N. and S. line, 70 lks. S. of Cor. S. 89° 30' W. on true line	
39.95	Set basalt stone, 9 x 10 x 12, for $\frac{1}{4}$ Sec. Cor.	
46.00	Bottom of ravine, course N.W.	
74.00	Summit of ridge, course N.	
79.91	To post Cor.	
	Land; broken, good grass	
	Soil; poor, 2nd rate.	
	W. on random bet. Secs. 18 & 19	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
76.81	Intersected N. and S. line, 48 lks. S. of post Cor. S. 89° 31' E. on true line	
36.81	Set post Cor. for $\frac{1}{4}$ Sec. Cor.; deposited marked stone & raised stone mound as per instructions.	
76.81	To post Cor.	
	Land; broken, good grass	
	Soil; 2nd rate.	
	N. bet. Secs. 17 & 18	
40.00	Set post Cor. for $\frac{1}{4}$ Sec. in ravine, course N.; deposited marked stone, and raised stone mound as per instructions.	
80.00	Set post Cor. for Secs. 7, 8, 17 & 18, deposited marked stone and raised stone mound as per instructions.	