

Resurvey of portion of the E. Bdy. of T. 4 N., R. 37 E., W.M.

Chains		Feet
	<p>Mountainous or heavily timbered land or land covered with dense undergrowth and exceptionally difficult to survey.</p> <p>78.72 chs.</p> <p style="text-align: right;">July 20, 1905.</p> <hr/> <p>Extracts from supplemental field Notes, E. bdy. of T 4 N., R 38 E., W.M. As surveyed by same surveyor, contract and date.</p> <hr/> <p style="text-align: center;"><u>Cor. of Secs. 19, 24, 25 & 30</u></p> <p>In making my original returns, through clerical error, I failed to describe this cor. as established by me. The following is a description of the Cor. as it now stands:</p> <p style="padding-left: 40px;">A fir tree, 24 ins. diam., marked as described by the Surveyor General.</p> <p>The bearing tree in Sec. 30, is still standing, and brs. and is marked as described by the Surveyor General. The other 3 witness trees are dead; in their places I marked the following trees:</p> <p style="padding-left: 80px;">A fir, 10 ins. diam., brs. N. 77° E., 125 lks. dist. marked T 4 N R 38 E S 19 B T</p> <p style="padding-left: 80px;">A fir, 18 ins. diam. brs S. 65° W., 65 lks. dist. marked T 4 N R 37 E S 25 B T</p> <p style="padding-left: 80px;">A fir, 12 ins. diam. brs. N. 82° W., 22 lks. dist. marked T 4 N R 37 E S 24 B T</p> <hr/> <p>Retrace bet. Secs. 19 & 24</p> <p>From the Cor. of Secs. 19, 24, 25 & 30, I retrace N. 46° E. bet. Secs. 19 & 24.</p> <p>40.20 Intersect the $\frac{1}{4}$ Sec. Cor.</p> <p>I continue retrace N. 10° E. bet. Secs. 19 & 24.</p> <p>78.85 Intersect the Cor. of Secs. 13, 18, 19 & 24.</p> <p>The $\frac{1}{4}$ Sec. Cor. as reestablished by me is out of position, but it was reestablished in its original position and the Tp. W. has been subdivided; therefore I had no authority to change the position of the old $\frac{1}{4}$ Sec. Cor., but in accordance with the Manual reestablished it at</p>	