

## Extracts from supplemental Field Notes, E. Bdy of T 4 N R 37 E., W.M.

Chains		Feet
	its original location.	
	Subdivisional Lines of T 4 N., R. 37 E., W.M. As surveyed by Wm. H. Odell, U.S. Deputy Surveyor Under Contract No. 114, Dated July 2nd, 1866.	
	Field Notes of a part of the subdivisional lines of Tp. 4 N. of the Base Line of R37 E. of W.M. Commencing at the S.E. Cor. of Sec. 32 N. bet. Secs. 32 & 33  Var. 19° 30' E.	
40.00	Set post Cor. for $\frac{1}{4}$ Sec. from which A pine, 12 ins diam. brs. N. 84° W., 18 lks. A fir, 10 ins. diam. brs. N. 81° E., 26 lks.	
80.00	Set post Cor for Secs. 28, 29, 32 & 33, from which A fir, 8 ins. diam. brs. S. 68° W., 27 lks. A fir, 8 ins. diam. brs. S. 75° E., 21 lks. A fir, 20 ins. diam. brs. N. 30° W., 52 lks. A fir, 8 ins. diam. brs. N. 20° E., 56 lks.  Land; gently rolling Timber; excellent, small growth, fir, larch and pine. Undergrowth the same.	
	N. bet. Secs. 28 & 29  Var. 20° E.	
3.75	Spring branch, 2 lks. wide, course W.	
40.00	Set post Cor. for $\frac{1}{4}$ Sec., from which A fir, 12 ins. diam. brs. N. 15° W., 10 lks. A fir, 14 ins. diam. brs. S. 20° E., 17 lks.	
80.00	Set post Cor. for Secs. 20, 21, 28 & 29, from which A fir, 12 ins. diam. brs. N. 36° E., 70 lks. A fir, 15 ins. diam. brs. N. 47° W., 30 lks. A larch, 20 ins. diam. brs. S. 35° W., 25 lks. A fir, 10 ins. diam. brs. S. 61° E. 40 lks.  Land; gently rolling, Good timber, fir, larch and pine Small growth very thick Oct. 12, 1866	