

Part of Subdivisional Lines of T. 4 N., R. 37 E., W.M.

Chains		Feet
	Timber, scattering pine, Very little undergrowth.	
	<hr/>	
	N. bet. Secs. 17 & 18	
40.00	Set post Cor. for $\frac{1}{4}$ Sec.; drove charred stake, and raised stone mound as per instructions.	
51.00	Bottom of ravine, course N.W.	
80.00	Set post Cor. for Secs. 7, 8, 17 & 18; drove charred stake made stone as per instructions.	
	Land; very broken, good grass Soil; rocky.	
	<hr/>	
	W. on random bet. Secs: 7 & 18	
		Var. 21° E.
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
80.72	Intersected N. & S. line, 48 lks. N. of Post Cor. N. 89° 39' E. on true line	
40.72	Set post Cor. for $\frac{1}{4}$ Sec.; drove charred stake, and raised mound of stone, as per instructions.	
70.00	Bottom of ravine, course N.W.	
80.72	To post Cor. Land; broken, good grass Soil; 2nd rate.	
		Oct. 22, 1866.
	<hr/>	
	At least two tiers of Secs. adjoining on the E. in this Tp. should be subdivided, because of the valuable timber but the lateness of the season renders it impracticable to prosecute the surveys farther.	
	<hr/>	
	Subdivisional Lines of T 4 N., R. 37 E., W.M. As surveyed by Geor. S. Pershin, U.S. Deputy Surveyor Under contract No. 332, Dated July 29, 1879.	
	<hr/>	
	I begin at the Cor. of Secs. 35 & 36 on the S. Bdy. of the Tp. and with Burts Improved Solar Compass, I run N. bet. Secs. 35 & 36	