

Subdivisional Lines of T 4 N R 37 E., W.M.

Chains		Feet
	A fir, 14 ins. diam. brs. N. 8° E., 168 lks. dist. No tree on S. side.	
58.00	Spring branch, course N.W.	
67.50	" " " N.	
80.26	The Cor. to Secs. 23, 24, 25 & 26. Land; surface extremely broken and mountainous. Soil; 3rd rate and worthless. Some good timber, but mostly scattering, fir, tamarack and spruce.	
<hr/>		
	N. bet. Secs. 34 & 35 Var. 20° 15' E.	
23.00	Spring branch, course W.	
37.50	Wagon road to Weston, course, S.E. and N.W.	
40.00	Set fir post on slight N. slope for $\frac{1}{4}$ Sec. Cor. A spruce, 11 ins. diam. brs. S. 43° E., 6 lks. dist. A spruce, 6 ins. diam. brs. S. 28° W., 15 lks. dist.	
42.50	Cabin, 20 lks. E.	
47.00	Brook, 4 lks. wide, course, W.	
80.00	Set fir post on level for cor. to Secs. 26, 27, 34 & 35. A fir, 8 ins. diam. brs. N. 47° E., 62 lks. dist. A fir, 8 ins. diam. brs. S. 20° E., 10 lks. dist. A fir, 24 ins. diam. brs. S. 44° W., 34 lks. dist. A fir, 20 ins. diam. brs. N. 50° W., 42 lks. dist. Land; surface, rolling, mountain table land Soil; 3rd rate. Heavy timber, fir, tamarack, spruce and hemlock Alder and yew underbrush.	
<hr/>		
	E. on a random line bet. Sec. 26 & 35 Var. 20° E.	
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.	
80.68	Intersected N. & S. line, 48 lks. S. of Cor. to Secs. 25, 26, 35 & 36, from which Cor. I run S. 89° 39' W. on a true line bet. Secs. 26 & 35 Var. 19° 00' E.	